

One State's Experience with Non Transmission Alternative Solutions

The Boothbay, Maine NTA Pilot

Dr Bruce Williamson, Commissioner

Faith Huntington, Director, Electric and Gas Industries


Denis Bergeron, Senior Analyst

Maine Public Utilities Commission

National Council on Electricity Policy (NCEP) Annual Meeting, Denver, May 8, 2018.

Any views herein are those of the authors provided as illustrative material for discussions, and as such do not represent or reflect official positions of the MPUC staff or its Commissioners.

Boothbay NTA pilot location




What is the policy backdrop that created the opportunity for the Boothbay Pilot?

- Merchant wind generation in central and northern Maine, load in southern New England
- Utility forecast of risks of imbalances on existing transmission
- Corrective actions might be traditional resources such as transmission upgrades, changes operational changes, addition of generation, or special protection systems.
- Boothbay Peninsula was one of several areas where expected load growth suggested a need for transmission upgrade on a radial
- NTA - Corrective actions may also be “non-transmission” or non-traditional solutions.
 - Rate applications
 - Distributed generation
 - Energy Efficiency
 - Storage
 - Demand response

Pilot project objectives – overview

- The Commission's initial approval of the Pilot rested on discovering information on the following issues;
 - Whether and what type of NTAs can be acquired at a reasonable cost to meet reliability requirements.
 - Whether and what were the best means by which the new advanced metering systems being deployed could provide the information and communications requirements to support NTA solutions.
 - Whether NTAs are capable of responding to provide grid reliability service.
 - Whether the Pilot's results can be scaled to meet requirements of other regions in Maine.

Policy Backdrop - Boothbay NTA Pilot



What was done? Who was involved? What went well and why?

- MPRP project transmission models indicated performance issues in Boothbay at a projected local area peak of 35.4 MW (2007 est).
- Legislation reacting to the MPRP project permitted the MPUC to consider allowing a “Smart Grid” coordinator.
- The stipulated settlement to the transmission proceeding anointed a sole source entity called “GridSolar” to serve as the Smart Grid Coordinator to develop non-transmission alternatives in Boothbay plus two other possible future locations.
- 2 MW of various non transmission measures were proposed to avoid the 35.4 MW critical load level peak.

Pilot project resources utilized

Resource	Capacity (kW)	Cost (\$/kW/Mo.)	Performance
Energy Efficiency	256	\$27.5	Consistent with expectations
Solar PV	211	\$49.8	Consistent with expectations – fine tuning is possible.
Backup Generator	455	\$17.4	Generally consistent performance – some start up issues.
Demand Response	23	\$110	Difficulty confirming effectiveness of the response.
Energy Storage	500	\$168.7	Initial start up issues and most expensive resource, but also most versatile and effective.
Load Shifting	230	\$110	Difficulty confirming effectiveness of the response.
Total	1,675		

Operational experience

- Multiple resources at different costs were explored in the Pilot. In a competitive NTA process, it's reasonable to assume more cost effective resources would be selected.
- Short term duration of the Pilot may have distorted costs of resources that might be acquired for a longer duration project.
- Battery storage was the most expensive, but also the most effective resource. Battery costs continue their rapid decline – likely a place for battery resources in future NTAs
- Additional analytical tools are needed to understand the extent to which these results can be scaled to meet needs in different locations or regionally
 - Counterfactuals will always be challenging and often contentious – but very important
- Had a critical need arisen, some of the minor resource performance problems observed in the pilot may have affected reliability
- AMI Metering objective was never tested in the pilot. GridSolar developed and relied on its own communications system rather than utilize the host utility AMI/EMS network infrastructure.

Pilot conclusions

- NTAs might defer or reduce the stranded cost problem that can be created by lumpy transmission investments
- NTA potentially bring more modular, flexible demand and supply components.
 - Caveat - LT Contracts carry their own potential for stranded costs!
- Operational problems with some NTA resources suggest a need for redundant resources, or a larger reserve margin, to mitigate these problems.
- Communication among participating entities can pose challenges - the entire process was lengthy and politically contentious – looking for the adults in the room.
- NTA requirements and feasibility are highly specific to load characteristics of the NTA area.
- Further assessment of NTA solutions through the use of pilot projects is warranted.

Lessons Learned – Institutional

- Utilities receive higher allowed returns for transmission investment than distribution system investment.
- Smart Grid Coordinator was considered by MPUC as requested by legislature
 - New institution, contracting authority was proposed to offset any imbalance utilities might have
 - As proposed, could it introduce its own bias based on for-profit project advocacy and project development?
- MPUC - grid coordinator duplicates capabilities, ultimately can increase ratepayer costs, and bypass effective protections for ratepayers.
 - The time is right to get the incentive structure and rate design problem right.
 - Utilities see the writing on the wall.

What impact has the activity or initiative had in the state and on the grid?

- The forecasted critical area load level of 35.4 MW used in the transmission modelling never materialized – no way to test proposed load modification measures
- When tested for performance, technologies installed performed reasonably well
 - Some start up and communication issues were observed
 - Measurement and verification issues with Demand Response resources were also an issue
- Add a reserve margin for active DR. Resource is not 100% reliable so consider building in a reserve margin to increase resource diversity.
- NTA resources are location specific – this location had highly seasonal load issues.

What would you advise other state level decision makers to do differently based on your experience?

- Sound, reliable, proven engineering and economic facts will be the scarcest resource of them all
- Forecasting can justify any solution, wire, non-wire, or hybrid.
- Are we being all too human?
 - Asymmetries in perception - planning NTAs and DER in growth areas is easy, just as with traditional solutions
 - These are locationally specific solutions, so load declines or no-growth - outmigration, aging population, industrial shifts, economic changes – can happen and lead to stranded costs - which compounds rate effects on underlying economic/demographic challenges
- Lessons from these efforts will be quickly forgotten without the process and record created within the regulatory framework